

**CITY AND COUNTY OF DENVER
DEPARTMENT OF PUBLIC WORKS
Engineering Division**

**CONTRACT NO. 201841976
PROJECT NAME: 2018 Citywide Contract Overlay**

ADDENDUM NO. 3 TO CONTRACT DOCUMENTS

Bidders are hereby instructed that the drawings, specifications, and other contract documents are modified, corrected, supplemented and/or superseded for the above mentioned project as hereinafter described in the following attachments:

Questions and Answers

Q1. In the pre-bid meeting there was talk of publishing the tabulation of quantities for each of the 4 different areas. I do not see this in any of the documents. Is this something that can be provided or will be provided?

A1. See Attached Spreadsheets

Q2. On Addendum #2, Question #14, I asked the question about the bid form showing a quantity of 5 lump sum for public information. We are used to seeing this item as 1 lump sum but 5 lump sums for 4 different areas has me confused. Should we expect to be paid the quantity of 1 lump sum per each area? (in which case there would only be 4 lump sums for the bid) Or 1 lump sum for the entire job? Would you please clarify?

A2. They will be paid 1 lump sum for PI

Q3. Textura, page BF-3, refers to adding the cost of using Textura to the bid line item labeled "Textura Payment System Fee", will this be added to the bid schedule?

A3. There is a line for the Textura fee. Please see page BF-3. This fee is added to your total bid.

Q4. Could you provide a quantity breakout for the Milling of 143,765 SY? Which street and quantity?

A4. See A1

Q5. The concrete curb ramps have no removals? Is it to be included in the placement of curb ramps?

A5. Curb ramps are remove and replace.

Q6. The high early concrete bid item does not have a removal item. Is it to be included in the placement of high early concrete?

A6. The high early is included in the total removal.

Q7. Asphalt breakout / location. Addendum 1 shared the concrete locations and quantities. Could you please do the same with the asphalt.

A7. See Attached Spreadsheets

Q8. Section 304, Base Course, page TS-31, there is no pay item for base course and described as incidental to the work. What should the contractor anticipate?

A8. Incidental base course

Q8. Traffic loops, lighting section on page TS-61 and TS-62, described as incidental to the work. Are the intersections all camera controlled?

A8. Traffic loops if needed will be installed by city crews.

Q9. What is the work hour restriction on this project? Is nights allowed anywhere?

A9. If the contractor wants to work at night they are more than welcome to apply for a noise variance.

This **ADDENDUM** shall be attached to, become a part of, and be returned with the Bid Proposal.



Lesley B. Thomas
City Engineer

6.4.18

Date

The undersigned bidder acknowledges receipt of this Addendum. The Proposal submitted herewith is in accordance with the stipulations set forth herein.

Contractor

DATE: _____

ADDENDUM NO. 3

Attachment A to Addendum No. 3

Engineers Estimates for 2018 Yosemite Hampden - I-225

Bid Item	Description	unit	bid quantity
202-00240	Removal of Asphalt Mat (Planing)	sy	60,755.56
202-00246	Removal of Asphalt Mat (Planing)(Special)	sy	3,000.00
202-00203	Removal of Curb and Gutter	lf	3,000.00
208-00050	Reset Ground Sign	ea	20.00
210-00810	Reset Inlet Grate and Frame	ea	15.00
210-04010	Adjust Manhole/Meter/Valve	ea	66.00
403-00720	HBP Patch	tn	300.00
403-09221	Stone Matrix Asphalt- Top Lift 2.5"	ton	8,331.00
412-00000	Testing	hr	43.00
412-00000	12 HR High Early Strength	cu yd	300.00
608-00010	Concrete Curb Ramp	sy	1,000.00
608-00015	Truncated Domes (Wet Set)	sf	502.00
609-21020	Curb & Gutter Type II, Section 2B	lf	1,500.00
623-00204	Traffic Control (Arterial)	ls/day	70.00
625-00001	Construction Surveying	Hour	100.00
627-00005	Epoxy Pavement Markings	gal	70.00
627-00310	Thermo Plastic Pavement Markings(X-Walk, Stop Line)	sf	5,000.00
627-30205	Preformed Plastic Pavement Markings Word Symbol	sf	1,300.00
630-00015	Uniformed Traffic Control	hr	100.00
630-80355	Portable Message Sign Panel	ls/day	14.00
626-01103	Public information	ls	1.00

Attachment C to Addendum No. 3

Engineers Estimates for Raleigh Dartmouth to Yale

Bid Item	Description	unit	bid quantity
202-00240	Removal of Asphalt Mat (Planing)	sy	16,411.00
202-00203	Removal of Curb and Gutter	lf	1,500.00
208-00050	Reset Ground Sign	sf	10.00
210-00810	Reset Inlet Grate and Frame	ea	4.00
210-04010	Adjust Manhole/Meter/Valve	ea	50.00
403-00720	HBP Patch	tn	300.00
403-34741	HBP Type Grading S (75) (PG 64-22)	ton	4,167.00
412-00000	Testing	hr	40
412-00000	12 HR High Early Strength Concrete	cu yd	66
608-00010	Concrete Curb Ramp	sy	200.00
608-00015	Truncated Domes (Wet Set)	sf	400.00
609-21020	Curb & Gutter Type II, Section 2B	lf	1,600.00
623-00204	Traffic Control (Collector)	ls/day	40.00
625-00001	Construction Surveying	Hour	50.00
627-00005	Epoxy Pavement Markings	gal	10.00
627-00310	Thermo Plastic Pavement Markings(X-Walk, Stop Line)	sf	1,000.00
627-30205	Preformed Plastic Pavement Markings Word Symbol	sf	250.00
630-00015	Uniformed Traffic Control	hr	50.00
630-80355	Portable Message Sign Panel	ls/day	14.00
626-01103	Public information	ls	1.00

Attachment D to Addendum No. 3

Engineers Estimates for 40th - 42nd Himalaya to Picadilly

Bid Item	Description	unit	bid quantity
202-00240	Removal of Asphalt Mat (Planing)	sy	33,444.44
202-00246	Removal of Asphalt Mat (Planing)(Special)	sy	1,500.00
202-00203	Removal of Curb and Gutter	lf	1,600.00
208-00050	Reset Ground Sign	sf	10.00
210-00810	Reset Inlet Grate and Frame	ea	13.00
210-04010	Adjust Manhole/Meter/Valve	ea	115.00
403-00720	HBP Patch	tn	300.00
403-34741	HBP Type Grading S (75) (PG 64-22)	ton	6,933.00
412-00000	Testing	hr	50.00
412-00600	12 Hr High Early Strength Concrete	sy	100.00
608-00010	Concrete Curb Ramp	sy	600.00
608-00015	Truncated Domes (Wet Set)	sf	200.00
609-21020	Curb & Gutter Type II, Section 2B	lf	1,900.00
623-00204	Traffic Control (Collector)	ls/day	40.00
625-00001	Construction Surveying	Hour	50.00
627-00005	Epoxy Pavement Markings	gal	10.00
627-00310	Thermo Plastic Pavement Markings(X-Walk, Stop Line)	sf	1,000.00
627-30205	Preformed Plastic Pavement Markings Word Symbol	sf	250.00
630-00015	Uniformed Traffic Control	hr	50.00
630-80355	Portable Message Sign Panel	ls/day	14.00
626-01103	Public information	ls	1.00

	Testing	ls	5,000.00
--	---------	----	----------