



**CITY AND COUNTY OF DENVER
DEPARTMENT OF PUBLIC WORKS**

CONTRACT NO. 201524769

STATEMENT OF QUANTITIES

| <u>Item No.</u> | <u>Description</u> | <u>Estimated Quantity</u> | |
|-----------------|--|---------------------------|----|
| 202-00001 | Removal of Structure | 15 | EA |
| 202-00019 | Removal of Inlet | 15 | EA |
| 202-00195 | Removal of Median cover | 6 | SY |
| 202-00200 | Removal of Sidewalk | 5,145 | SY |
| 202-00201 | Removal of Curb Head | 168 | LF |
| 202-00203 | Removal of Curb & Gutter | 10,911 | LF |
| 202-00204 | Removal of Combination Curb, Gutter & Walk | 3,375 | LF |
| 202-00206 | Removal of Concrete Curb Ramp | 3,729 | SY |
| 202-00210 | Removal of Concrete Pavement | 6,735 | SY |
| 202-00220 | Removal of Asphalt Mat | 3,165 | SY |
| 203-00100 | Muck Excavation | 1,293 | CY |
| 203-02330 | 3-man Labor Crew | 45 | HR |
| 208-00050 | Storm Drain Inlet Protection | 369 | EA |
| 210-00810 | Reset Ground Sign | 24 | EA |
| 210-04010 | Adjust Manhole/Meter/Valve | 69 | EA |
| 210-04020 | Reset Inlet Grate, Frame & Adjustable Curb Box (New Casting) | 159 | EA |
| 212-00050 | Sodding | 2,889 | SF |
| 212-01200 | Landscape Restoration | 2,889 | SF |



**CITY AND COUNTY OF DENVER
DEPARTMENT OF PUBLIC WORKS**

CONTRACT NO. 201524769

STATEMENT OF QUANTITIES

| Item No. | Description | Estimated Quantity | |
|-----------------|--|---------------------------|-----|
| 304-06000 | Aggregate Base Course | 2,625 | Ton |
| 403-00720 | HBP Patch | 975 | Ton |
| 412-00600 | 6 Inch Concrete Pavement | 7,875 | SY |
| 412-00800 | 8 Inch Concrete Pavement | 1,050 | SY |
| 603-01150 | 15 Inch Reinforced Concrete Pipe (CIP) | 105 | LF |
| 603-01180 | 18 Inch Reinforced Concrete Pipe (CIP) | 105 | LF |
| 604-16050 | Type 14 Curb Inlet (6 Foot) | 6 | EA |
| 604-16050 | Type 14 Curb Inlet (9 Foot) | 6 | EA |
| 604-16050 | Type 16 Curb Inlet (Single)(4 Foot 8 Inches) | 12 | EA |
| 604-16050 | Type 16 Curb Inlet (Single)(8 Foot 5 Inches) | 6 | EA |
| 604-30005 | 4 Foot DIA Manhole Slab Base (5 Foot) | 21 | EA |
| 604-39010 | 4 Foot DIA Manhole Slab Base (10 Foot) | 6 | EA |
| 608-00000 | Concrete Sidewalk (6 Inch) | 4,719 | SY |
| 608-00005 | Concrete Sidewalk (Special) | 1,125 | SY |
| 608-00010 | Concrete Curb Ramp | 2,100 | SY |
| 609 | Intersection Valley Pan (8 Foot)(10 Inches) | 90 | LF |
| 609-20100 | Variable Height Curb Head W/Reinforcement | 258 | LF |
| 609-21020 | Curb & Gutter Type II, Section 2B | 5,574 | LF |
| 609-21023 | Curb & Gutter Type IIB (9 Inch) Curbhead | 2,139 | LF |



**CITY AND COUNTY OF DENVER
DEPARTMENT OF PUBLIC WORKS**

CONTRACT NO. 201524769

STATEMENT OF QUANTITIES

| Item No. | Description | Estimated Quantity | |
|-----------------|---|---------------------------|-----|
| 609-22021 | Combination Curb, Gutter & Sidewalk (2 Foot - 8 Inch) | 1,239 | LF |
| 609-22025 | Combination Curb, Gutter & Sidewalk (3 Foot - 11 Inch) | 1,125 | LF |
| 610-00024 | Median cover Material (4 Inch Concrete)(#67 or #57 Aggregate) | 1,269 | SF |
| 613-07000 | Reset Pull Box | 69 | EA |
| 623-00204 | Sprinkler system-Adjust Sprinkler | 288 | EA |
| 623-00204 | Sprinkler system-New Sprinkler Head | 159 | EA |
| 623-00505 | Sprinkler System-Irrigation Reconstruction | 630 | LF |
| 629-01065 | Survey Monument | 30 | EA |
| 630-00013 | Traffic Control Management | 315 | Day |
| 630-80341 | Construction Traffic Sign (Panel Size A) | 309 | EA |
| 630-80344 | Construction Traffic Sign (Panel Size B) | 372 | EA |
| 630-80355 | Portable Message Sign Panel | 6 | EA |
| 630-80358 | Advanced Warning Flashing or Sequencing Arrow Panel (C Type) | 45 | EA |
| 630-80360 | Drum Channelizing Device | 2,286 | EA |
| 630-80363 | Drum Channelizing Device (With Light)(Flashing) | 372 | EA |
| 630-80380 | Traffic Cone | 3,090 | EA |
| 630-00003 | Uniformed Traffic Control | 768 | HR |



**CITY AND COUNTY OF DENVER
DEPARTMENT OF PUBLIC WORKS**

CONTRACT NO. 201524769

STATEMENT OF QUANTITIES

| <u>Item No.</u> | <u>Description</u> | <u>Estimated Quantity</u> | |
|-----------------|---|---------------------------|-----------|
| ALLOWANCE 1 | | | |
| A/W 01 | Construction Surveying | 1 | Allowance |
| ALLOWANCE 2 | | | |
| A/W 02 | Mobilization (Percent of Task Order Construction Bid Items) | 1 | Allowance |