



**DENVER**  
THE MILE HIGH CITY

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**  
**201845779**  
**2018 Citywide Bond Concrete Repair**

**STATEMENT OF QUANTITIES**

<u>Item No.</u>	<u>Description</u>	<u>Estimated</u>	<u>Quantity</u>
202-00019	REMOVAL OF INLET	10	EA
202-00033	REMOVAL OF SIPHON	10	EA
202-00200	REMOVAL OF SIDEWALK	3,750	SY
202-00201	REMOVAL OF CURBHEAD	2,000	LF
202-00203	REMOVAL OF CURB AND GUTTER	5,500	LF
202-00204	REMOVAL OF COMBINATION CURB, GUTTER AND WALK	4,000	LF
202-00208	REMOVAL AND RESET FLAGSTONE (INCLUDES SALVAGE AND STORAGE)	500	SY
202-00210	REMOVAL OF CONCRETE PAVEMENT	2,500	SY
202-00220	REMOVAL OF ASPHALT MAT	7,500	SY
202-01000	REMOVAL OF FENCE	500	LF
202-05021	TRIP HAZARD SAWING (>5 LOCATIONS 1 MONTH COMPLETION)	100	IN-FT
202-05020	TRIP HAZARD SAWING (<= 5 LOCATIONS 1 WEEK COMPLETION)	100	IN-FT
203-00200	UNCLASSIFIED EXCAVATION	2,500	CY
203-02330	3-MAN LABOR CREW	300	HR
206-00065	STRUCTURE BACK FILL (FLOW FILL)	150	CY
208-00050	STORM DRAINAGE INLET PROTECTION	750	EA
210-00810	RESET GROUND SIGN	250	EA



**DENVER**  
THE MILE HIGH CITY

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**  
**201845779**  
**2018 Citywide Bond Concrete Repair**

**STATEMENT OF QUANTITIES**

<b>Item No.</b>	<b>Description</b>	<b>Estimated</b>	<b>Quantity</b>
210-04010	ADJUST MANHOLE/METER/VALVE/PULLBOX	60	EA
210-04011	ADJUST INLET FRAME AND ADJUSTABLE CURBHEAD	60	EA
210-04020	RESET INLET GRATE,FRAME, AND ADJUSTABLE CURB BOX (NEW CASTING)	100	EA
212-00050	SODDING	500	SF
212-01200	RESTORE LANDSCAPING	2,500	SF
212-01201	AMENDED TOP SOIL OR LANDSCAPE PLANTER'S SOIL MIX	250	CY
304-06000	AGGREGATE BASE COURSE	1,000	TON
403-00720	HBP PATCH/OVERLAY	2,000	TON
412-00000	24-HOUR HIGH EARLY STRENGTH CONCRETE	2,400	CY
412-00001	ADD PIGMENT TO CONCRETE	100	CY
412-00100	GEO TECH MATERIAL TESTING CONCRETE	50	EA
412-00400	4" CONCRETE PAVEMENT	150	SY
412-00600	6" CONCRETE PAVEMENT	2,500	SY
412-00800	8" CONCRETE PAVEMENT	500	SY
412-01000	10" CONCRETE PAVEMENT	200	SY
412-01200	12" CONCRETE PAVEMENT	200	SY
413-00100	CONCRETE PATCHING (STRUCTURAL SURFACE REPAIR <2" DEPTH)	200	SF-IN



**DENVER**  
THE MILE HIGH CITY

CITY AND COUNTY OF DENVER  
DEPARTMENT OF PUBLIC WORKS  
201845779

2018 Citywide Bond Concrete Repair

STATEMENT OF QUANTITIES

<u>Item No.</u>	<u>Description</u>	<u>Estimated</u>	<u>Quantity</u>
601-00100	PAVESTONE STACKED PRE-CAST WALL BLOCK	500	SF
601-00400	REINFORCED VARIABLE HEIGHT CONCRETE RETAINING WALL	1,500	SF
601-06150	CONCRETE PATCHING (STRUCTURAL CURB REPAIR)	500	LF
603-01150	15" REINFORCED CONCRETE PIPE (RCP)	50	LF
603-01180	18" REINFORCED CONCRETE PIPE (RCP)	50	LF
604-14050	NUMBER 14 INLET (L=6')	10	EA
604-16050	SINGLE NUMBER 16 INLET	10	EA
608-00000	CONCRETE SIDEWALK	2,500	SY
608-00010	CONCRETE CURB RAMP	8,500	SY
608-00018	TRUNCATED DOMES (SPECIAL CAST IRON) MATERIAL ONLY	500	SF
609-20000	CONCRETE GUTTER OVERLAY	3,000	LF
609-21020	CURB & GUTTER TYPE II, SECTION 2B	5,500	LF
609-21023	CURB & GUTTER TYPE IIB (9") CURBHEAD	300	LF
609-22021	COMBINATION CURB, GUTTER & SIDEWALK (2- '8")	3,500	LF
609-22025	COMBINATION CURB, GUTTER & SIDEWALK (3'-11")	400	LF
610-00026	MEDIAN COVER MATERIAL (6" PATTERNED COLORED CONCRETE)	100	SY



**DENVER**  
THE MILE HIGH CITY

**CITY AND COUNTY OF DENVER**  
**DEPARTMENT OF PUBLIC WORKS**  
**201845779**  
**2018 Citywide Bond Concrete Repair**

**STATEMENT OF QUANTITIES**

<u>Item No.</u>	<u>Description</u>	<u>Estimated</u>	<u>Quantity</u>
613-07000	RESET PULL BOX	50	EA
614-72875	LOOP DETECTOR WIRE	50	LF
623-00204	SPRINKLER SYSTEM/ADJUST SPRINKLER HEAD	500	EA
623-00205	SPRINKLER SYSTEM/NEW SPRINKLER HEAD	500	EA
623-00505	SPRINKLER SYSTEM/IRRIGATION RECONSTRUCTION	7,500	LF
630-00000	TRAFFIC CONTROL - ARTERIAL/COLLECTOR	50	DAY
630-00002	TRAFFIC CONTROL - LOCAL	100	DAY
630-00003	TRAFFIC CONTROL - UNIFORMED TRAFFIC CONTROL	20	HR