

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

STATEMENT OF QUANTITIES

Schedule A – Mill Levy 16A			
ITEM NO.	DESCRIPTION	ESTIMATED	UNIT TYPE
202-00011	TREE TRIMMING	10	EA
202-00019	REMOVAL OF INLET	7	EA
202-00035	REMOVAL OF PIPE	51	LF
202-00195	REMOVAL OF MEDIAN COVER	94	SY
202-00200	REMOVAL OF SIDEWALK	480	SY
202-00203	REMOVAL OF CURB AND GUTTER	1,044	LF
202-00206	REMOVAL OF CONCRETE CURB RAMP	166	SY
202-00220	REMOVAL OF ASPHALT MAT	598	SY
202-00828	REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1	LS
203-01597	POTHOLING	180	EA
208-00002	EROSION LOG (12 INCH)	150	LF
208-00035	AGGREGATE BAG	98	LF
208-00051	STORM DRAIN INLET PROTECTION (TYPE 1)	168	LF
208-00103	REMOVAL AND DISPOSAL OF SEDIMENT (LABOR)	72	HR
208-00105	REMOVAL AND DISPOSAL OF SEDIMENT (EQUIPMENT)	72	HR
208-00106	SWEEPING (SEDIMENT REMOVAL)	48	HR
208-00205	EROSION CONTROL SUPERVISOR	72	HR
210-04020	MODIFY INLET	16	EA
212-00000	TREE RETENTION AND PROTECTION	22	EA
403-00720	HOT MIX ASPHALT (PATCHING) (ASPHALT)	98	TON
503	VACUUM CAISSON (24 INCH)	28	LF

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

STATEMENT OF QUANTITIES

503-00024	DRILLED CAISSON (24 INCH)	49	LF
503	VACUUM CAISSON (36 INCH)	15	LF
503-00036	DRILLED CAISSON (36 INCH)	160	LF
603-01155	15 INCH REINFORCED CONCRETE PIPE (COMPLETE IN PLACE)	61	LF
603-01185	18 INCH REINFORCED CONCRETE PIPE (COMPLETE IN PLACE)	41	LF
604-16005	INLET TYPE 16 (5 FOOT)	4	EA
604-19105	INLET TYPE 14(R) (5 FOOT)	4	EA
604-30005	MANHOLE SLAB BASE (5 FOOT)	3	EA
608-00006	CONCRETE SIDEWALK (6 INCH)	651	SY
608-00010	CONCRETE CURB RAMP	282	SY
609-21020	CURB AND GUTTER TYPE 2 (SECTION II-B)	852	LF
610-00020	MEDIAN COVER MATERIAL (PATTERNED CONCRETE)	1,224	SF
613	ELECTRIC METER PEDESTAL CABINET AND BASE	6	EA
613-00306	3 INCH ELECTRICAL CONDUIT (BORED)	2,215	LF
613-01200	2 INCH ELECTRICAL CONDUIT (PLASTIC)	263	LF
613-01300	3 INCH ELECTRICAL CONDUIT (PLASTIC)	535	LF
613-07000	PULL BOX (SPECIAL)	12	EA
613-10000	WIRING	1	LS
614	LUMINAIRE (LED)	24	EA
614	TRAFFIC SIGNAL CONTROLLER AND CABINET	6	EA
614	EMERGENCY VEHICLE TRAFFIC SIGNAL PRIORITY CONTROL SYSTEM	6	EA

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

STATEMENT OF QUANTITIES

614	ETHERNET MANAGED SWITCH	6	EA
614-00011	SIGN PANEL (CLASS I)	16	SF
614-00012	SIGN PANEL (CLASS II)	453	SF
614-70150	PEDESTRIAN SIGNAL FACE (16) (COUNTDOWN)	48	EA
614-70336	TRAFFIC SIGNAL FACE (12-12-12)	51	EA
614-81000	TRAFFIC SIGNAL LIGHT POLE STEEL	11	EA
614-81120	TRAFFIC SIGNAL-LIGHT POLE STEEL (1-20 FOOT MAST ARM)	2	EA
614-81125	TRAFFIC SIGNAL-LIGHT POLE STEEL (1-25 FOOT MAST ARM)	2	EA
614-81130	TRAFFIC SIGNAL-LIGHT POLE STEEL (1-30 FOOT MAST ARM)	3	EA
614-81135	TRAFFIC SIGNAL LIGHT POLE STEEL (1-35 FOOT MAST ARM)	3	EA
614-81140	TRAFFIC SIGNAL-LIGHT POLE STEEL (1-40 FOOT MAST ARM)	3	EA
614-86105	TELEMETRY (FIELD)	6	EA
614-86800	UNINTERRUPTED POWER SUPPLY	6	EA
614-87333	CLOSED CIRCUIT TELEVISION CAMERA (TRAFFIC SURVEILLANCE)	6	EA
625-00000	CONSTRUCTION SURVEYING	1	LS
626-00000	MOBILIZATION	1	LS
627-00005	EPOXY PAVEMENT MARKINGS	6	GAL
627-30410	PREFORMED THERMOPLASTIC PAVEMENT MARKING (XWALK-STOPLINE)	3,134	SF
629-01001	SURVEY MONUMNET TYPE 1	24	EA
630	CONSTRUCTION TRAFFIC CONTROL	1	LS

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

STATEMENT OF QUANTITIES

630-00003	UNIFORMED TRAFFIC CONTROL	96	HR
700-70310	AW LANDSCAPING	1	A/A
700-70380	AW EROSION CONTROL	1	A/A
700-70589	AW ENVIRONMENTAL HEALTH AND SAFETY MANAGEMENT	1	A/A
Schedule B – Mill Levy 17A			
ITEM NO.	DESCRIPTION	ESTIMATED	UNIT TYPE
202-00200	REMOVAL OF SIDEWALK	24	SY
202-00203	REMOVAL OF CURB AND GUTTER	53	LF
202-00206	REMOVAL OF CONCRETE CURB RAMP	20	SY
202-00220	REMOVAL OF ASPHALT MAT	13	SY
202-00705	REMOVAL OF LIGHT STANDARD FOUNDATION	1	EA
202-00810	REMOVAL OF GROUND SIGN	1	EA
202-00821	REMOVAL OF SIGN PANEL	1	EA
203-01598	POTHOLING	25	EA
208-00054	STORM DRAIN INLET PROTECTION (TYPE II)	3	EA
212-00100	TREE PROTECTION	4	EA
212-01210	LANDSCAPE RESTORATION	292	SF
403-00720	HOT MIX ASPHALT (PATCHING) (ASPHALT)	7	TON
503-00036	DRILLED SHAFT (36 INCH)	39	LF
608-00006	CONCRETE SIDEWALK (6 INCH)	23	SY
608-00010	CONCRETE CURB RAMP	25	SY
609-21020	6" CURB AND GUTTER - 2' CATCH PAN	28	LF
610-00030	MEDIAN COVER MATERIAL (CONCRETE)	14	SF

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

STATEMENT OF QUANTITIES

613-00206	2 INCH ELECTRICAL CONDUIT (BORED)	377	LF
613-00300	3 INCH ELECTRICAL CONDUIT	216	LF
613-00306	3 INCH ELECTRICAL CONDUIT (BORED)	363	LF
613-07023	PULL BOX TYPE C (TRAFFIC COMM)	2	EA
613-07198	PULL BOX (SPECIAL) (INSTALL ONLY)	4	EA
613-10000	WIRING	1	LS
613-13065	LUMINAIRE (LED) (5400 LUMENS)	4	EA
613	ELECTRIC METER PEDESTAL CABINET AND BASE	1	EA
614-00011	SIGN PANEL (CLASS I)	42	SF
614-00035	SIGN PANEL (SPECIAL)	39	SF
614-70150	PEDESTRIAN SIGNAL FACE (16) (COUNTDOWN)	6	EA
614-70336	TRAFFIC SIGNAL FACE (12-12-12)	10	EA
614	TRAFFIC SIGNAL CONTROLLER AND CABINET	1	EA
614-72860	PEDESTRIAN PUSH BUTTON	6	EA
614-72866	EMERGENCY VEHICLE TRAFFIC SIGNAL PRIORITY CONTROL SYSTEM	1	EA
614-72886	INTERSECTION DETECTION SYSTEM (CAMERA) (FLIR)	3	EA
614-81000	TRAFFIC SIGNAL - LIGHT POLE STEEL	1	EA
614-81301	TRAFFIC SIGNAL - LIGHT POLE STEEL (1-30 FOOT MAST ARM) (INSTALL ONLY)	1	EA
614-81301	TRAFFIC SIGNAL - LIGHT POLE STEEL (1-35 FOOT MAST ARM) (INSTALL ONLY)	2	EA
614-86105	TELEMETRY (FIELD)	1	EA
614-86800	UNINTERRUPTED POWER SUPPLY	1	EA

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

STATEMENT OF QUANTITIES

614-87006	FIBER OPTIC TERMINATION PANEL (6 PANEL)	1	EA
614-87320	CCTV	1	EA
614-87690	ETHERNET MANAGED SWITCH	1	EA
620-00020	SANITARY FACILITY	1	EA
625-00000	CONSTRUCTION SURVEYING	1	LS
627-00005	EPOXY PAVEMENT MARKING	4	GAL
627-30205	THERMOPLASTIC PAVEMENT MARKING (WORD-SYMBOL)	72	SF
627-30210	THERMOPLASTIC PAVEMENT MARKING (XWALK-STOP LINE)	447	SF
629-01005	SURVEY MONUMENT (TYPE 5)	1	EA
630	TRAFFIC CONTROL MANAGEMENT	1	LS
A/W 01	ALLOWANCE - ELECTRIC SERVICE (FURNISH AND INSTALL)	1	A/A
A/W 02	ALLOWANCE - MOBILIZATION	1	A/A
A/W 03	ALLOWANCE - EROSION CONTROL	1	A/A