

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

**STATEMENT OF QUANTITIES**

<b>ITEM NO.</b>	<b>DESCRIPTION</b>	<b>ESTIMATED</b>	<b>UNIT TYPE</b>
202-1	Removal of Asphalt Mat (Edge Milling - 1" Tapered)	280,000	SY
202-2	Removal of Asphalt Mat (Milling - 2" Depth)	29,400	SY
210-1	Adjust Manhole	290	EA
210-2	Adjust Range Point Box	175	EA
403-1	Hot-In-Place Recycling and Repaving	664,000	SY
403-2	Rejuvenating Agent	52,920	GAL
403-3	Furnish Asphalt (Haul Only) (Haul Distance 1 to 5 miles)	2,430	TON
403-4	Furnish Asphalt (Haul Only) (Haul Distance 5 to 10 miles)	5,370	TON
403-5	Furnish Asphalt (Haul Only) (Haul Distance 10 to 15 miles)	34,300	TON
403-6	Furnish Asphalt (Haul Only) (Haul Distance 15 to 20 miles)	1,960	TON
403-7	Furnish Asphalt (Haul Only) (Haul Distance 20 to 25 miles)	1,470	TON
403-8	HBP Patching	146	TON
627-1	Waterborne Paint Marking	140	GAL
627-2	Epoxy Pavement Marking	196	GAL
627-3	Preformed Plastic Pavement Marking (Type 1)(In Laid) (Lane Lines)	880	SF
627-4	Thermoplastic Pavement Marking (Extruded) (Center & Edge Lines)	900	SF
627-5	Preformed Thermoplastic Pavement Marking (Xwalk - Stop Line)	4,400	SF
627-6	Preformed Thermoplastic Pavement Marking (Word Symbol)	530	SF
630-1	Traffic Control Arterial Streets	20	LS/DAY
630-2	Traffic Control Collector/Local Streets	75	LS/DAY
630-5	Uniformed Traffic Control	800	HR