

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

| |
|--------------------------------|
| STATEMENT OF QUANTITIES |
|--------------------------------|

| ITEM NO. | DESCRIPTION | ESTIMATED | UNIT TYPE |
|-----------|---------------------------------------------------------|-----------|-----------|
| 202-00204 | Removal of Asphalt Mat | 417,832 | SY |
| 202-00810 | Removal of Ground Sign | 10 | EA |
| 203-00100 | Storm Drainage Inlet Protection | 6 | EA |
| 208-00050 | Reset Ground Sign | 10 | SF |
| 210-00810 | Reset Inlet Grate and Frame | 4 | EA |
| 210-04010 | Adjust Manhole/Meter/Valve | 200 | EA |
| 403-00720 | HBP Patch | 400 | TON |
| 403-34741 | HBP Type Grading S (75) (PG 64-22) 2" | 41,500 | TON |
| 403-09221 | Stone Matrix Asphalt- Top Lift 2" | 5,100 | TON |
| 614-00009 | Install Sign Panel | 10 | EA |
| 614-00021 | Sign Panel (Furnish Only) | 10 | SF |
| 614-00216 | Steel Sign Post (2x2 Inch Tubing) | 10 | LF |
| 623-00204 | Traffic Control (Arterial) | 100 | LS/DAY |
| 623-00204 | Traffic Control (Collector) | 45 | LS/DAY |
| 626-80000 | Preformed Plastic Pavement Markings (Green) | 500 | SF |
| 627-00005 | Epoxy Pavement Markings | 100 | GAL |
| 627-00310 | Thermo Plastic Pavement Markings(X-Walk, Stop Line) | 10,000 | SF |
| 627-30205 | Preformed Plastic Pavement Markings Word Symbol | 2,000 | SF |
| 630-00003 | Uniformed Traffic Control | 100 | HR |
| 632-00000 | Public Information | 1 | LS |