

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

**STATEMENT OF QUANTITIES**

<b>ITEM NO.</b>	<b>DESCRIPTION</b>	<b>ESTIMATED</b>	<b>UNIT TYPE</b>
202-00035	REMOVAL OF PIPE	8	LF
202-00500.0	REMOVAL OF PORTIONS OF PRESENT STRUCTURE	1	EA
202-00810.0	RESET GROUND SIGN	8	EA
207-01110	BIORETENTION MEDIA	1,157	CY
208-00046	PRE-FABRICATED CONCRETE WASHOUT STRUCTURE (TYPE 1)	1	EA
208-00054	STORM DRAIN INLET PROTECTION (TYPE 2)	39	EA
208-00056	STORM DRAIN INLET PROTECTION (TYPE 3)	3	EA
214-00231	ADDITIONAL TREES - CCD FORESTRY	7	EA
250-00110	HEALTH AND SAFETY OFFICER	450	HR
403-00721	HOT MIX ASPHALT (PATCHING) (ASPHALT)	1,555	SY
601-01000.0	CONCRETE CLASS B	28	CY
603-01155	15 INCH REINFORCED CONCRETE PIPE (COMPLETE IN PLACE)	96	LF
603-01185	18 INCH REINFORCED CONCRETE PIPE (COMPLETE IN PLACE)	257	LF
608-00600.0	SPECIALTY CONCRETE - RAKED FINISH	518	SY
608-00005	CONCRETE SIDEWALK (SPECIAL) (4 INCH)	1,905	SY
608-00006.0	CONCRETE SIDEWALK (6 INCH)	227	SY
608-00005.0	CONCRETE SIDEWALK (SPECIAL) (8 INCH)	38	SY
608-00005.00	CONCRETE SIDEWALK (SPECIAL) ((SWA) 4" THK)	587	SY
608-00010.0	CONCRETE CURB RAMP	218	SY
609-24008.0	GUTTER TYPE 2 (8 FOOT)	608	LF
614-00012	SIGN PANEL (CLASS II)	9	SF
630-85040	IMPACT ATTENUATOR (TRUCK MOUNTED ATTENUATOR) (TEMPORARY)	2	EA
615-00700	HDPE WEIR	824	SF
623-01708	1 INCH BACKFLOW PREVENTER	7	EA
623-02008	1 INCH DRAIN VALVE	16	EA
626-01113	PUBLIC INFORMATION MANAGEMENT (TIER III)	275	DAY
630-00000.00	FLAGGING	4,400	HR
214-00005	LANDSCAPE MAINTENANCE (24 MONTH)	1	LS
202-00202	REMOVAL OF GUTTER	553	LF
202-00209	REMOVAL OF SIDEWALK (SWA)	5,282	SF
202-01301	REMOVAL OF METAL GRATE	7	EA
202-01302	REMOVE AND RESET BENCH	3	EA
202-00010	REMOVAL OF TREE	11	EA
202-00019	REMOVAL OF INLET	2	EA
202-00200	REMOVAL OF SIDEWALK	38,535	SF
202-00203	REMOVAL OF CURB AND GUTTER	796	LF
202-00206	REMOVAL OF CONCRETE CURB RAMP	1,245	SF
202-00220	REMOVAL OF ASPHALT MAT	28,499	SF
203-00000	UNCLASSIFIED EXCAVATION	1,364	CY
206-00520	FILTER MATERIAL (CLASS B)	50	CY

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

**STATEMENT OF QUANTITIES**

<b>ITEM NO.</b>	<b>DESCRIPTION</b>	<b>ESTIMATED</b>	<b>UNIT TYPE</b>
208-00106a	SWEEPING (SEDIMENT REMOVAL)	480	HR
208-00020	SILT FENCE	369	LF
208-00035	AGGREGATE BAG	252	LF
208-00051	STORM DRAIN INLET PROTECTION (TYPE 1)	10	EA
208-00070	VEHICLE TRACKING PAD	1	EA
208-00207	EROSION CONTROL MANAGEMENT	275	DAY
212-00005	SEEDING (NATIVE)	50	LB
212-00010	SEEDING (LAWN)	58	LB
212-00100	EXISTING TREE - OCF STANDARD TREE PROTECTION	7	EA
213-00008	MULCHING (WOOD CHIP)	675	SF
213-00067	ROCK MULCH (DECOMPOSED GRANITE)	17,085	SF
214-00225	DECIDUOUS SHADE TREE (2.5 INCH CALIPER)	51	EA
214-00226	FLOWERING ORNAMENTAL TREE (2.5 INCH CALIPER)	6	EA
214-00350	DECIDUOUS SHRUB (5 GALLON CONTAINER)	370	EA
214-00911	FLOWERING PERENNIALS (1 GALLON CONTAINER)	2,283	EA
214-01000	EMERGENT BULBS	1,269	EA
214-01320	ORNAMENTAL GRASSES (1 GALLON CONTAINER)	1,850	EA
240-00000	WILDLIFE BIOLOGIST	32	HR
250-00010	ENVIRONMENTAL HEALTH AND SAFETY MANAGEMENT	1	LS
250-00050	MONITORING TECHNICIAN	800	HR
412-00815	CONCRETE PAVEMENT (8 INCH) (REINFORCED)	1,366	SY
508-00520	INSULATION MATERIAL (2 INCH)	1,046	SF
514-01017	COMBINATION PEDESTRIAN AND TRAFFIC RAIL (SPECIAL)	111	LF
601-03050	CONCRETE CLASS D (WALL)	331	CY
603-50004	4 INCH PLASTIC PIPE	202	LF
603-50015	15 INCH PLASTIC PIPE	21	LF
603-50008	8 INCH PLASTIC PIPE	3,855	LF
603-50012	12 INCH PLASTIC PIPE	505	LF
604-13006	INLET TYPE 13 (5 FOOT)(SPECIAL)	6	EA
604-13505	INLET TYPE 13 (DOUBLE) (5 FOOT)	1	EA
604-19000	INLET SPECIAL	56	EA
604-19110	INLET TYPE R L 5 (10 FOOT)	2	EA
604-20005	AQUASWIRL - AS-2 (2.5' DIAMETER)	2	EA
604-20006	AQUASWIRL - AS-3 (3.5' DIAMETER)	1	EA
604-20007	AQUASWIRL - AS-4 (4.5' DIAMETER)	1	EA
604-20009	AQUASWIRL - AS-6 (6' DIAMETER)	1	EA
604-30010	MANHOLE SLAB BASE (10 FOOT)	3	EA
604-19105	INLET TYPE R L 5 (5 FOOT)	1	EA
604-19205	INLET TYPE R L 10 (5 FOOT)	1	EA

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

**STATEMENT OF QUANTITIES**

<b>ITEM NO.</b>	<b>DESCRIPTION</b>	<b>ESTIMATED</b>	<b>UNIT TYPE</b>
604-20011	PREFABRICATED CONTROL STRUCTURE (AGRIDRAIN)	56	EA
604-30005	MANHOLE SLAB BASE (5 FOOT)	1	EA
604-50150	PREFABRICATED JUNCTION STRUCTURE (NYLOPLAST BASIN - 18" DIAMETER)	57	EA
605-00042	4 INCH SLOTTED PIPE UNDERDRAIN	295	LF
605-83540	4 INCH PIPE UNDERDRAIN	325	LF
607-53173	FENCE CHAIN LINK (SPECIAL) (72 INCH)	2,000	LF
609-21020.0	CURB & GUTTER TYPE II, SECTION 2B	1,035	LF
614-00011	SIGN PANEL (CLASS I)	36	SF
614-01503	STEEL SIGN SUPPORT (2-INCH ROUND)(POST AND SOCKET)	12	EA
619-00001	3/4" WATER METER	1	EA
619-40060	3/4" COPPER PIPE	112	LF
619-77400	3/4" CURB STOP AND BOX	1	EA
619-77402	2" PLUG	1	EA
619-77412	12" PLUG	1	EA
619-10127	12 INCH WELDED STEEL PIPE (JACKED)	119	LF
619-40080	1 INCH COPPER PIPE	225	LF
619-40081	1 INCH COPPER PIPE (BORE)	395	LF
620-00002	FIELD OFFICE (CLASS 2)	1	EA
622-00253	CUSTOM STEEL 42" GUARD RAIL	4	EA
622-00270	BOLLARD	8	EA
622-00250	CUSTOM "FOLDED" STEEL END-WALLS	18	EA
622-00251	"FOLDED" STEEL BENCH	58	EA
623-00212	12 INCH POP-UP SPRAY SPRINKLER	503	EA
623-00600	1-1/2 INCH PLASTIC PIPE	5,300	LF
623-00601	1 INCH PLASTIC PIPE	4,200	LF
623-00602	2 INCH PLASTIC PIPE - (IRRIGATION/SLEEVE)	1,750	LF
623-00604	4 INCH PLASTIC PIPE - (IRRIGATION/SLEEVE)	1,600	LF
623-00607	2 INCH PLASTIC PIPE - (IRRIGATION/SLEEVE) (BORED)	860	LF
623-00608	4 INCH PLASTIC PIPE - (IRRIGATION/SLEEVE)(BORED)	725	LF
623-03108	1 INCH AUTOMATIC CONTROL VALVE	51	EA
623-04000	CONTROL WIRE 2-WIRE	5,300	LF
623-04002	POWER SOURCE WIRE	1,050	LF
623-04004	CONTROLLER DECODERS	51	EA
623-04005	GROUNDING LOCATION	31	EA
623-04008	1 INCH QUICK COUPLER VALVE	28	EA
623-04510	3/4 INCH BALL VALVE	51	EA
623-05012	1-1/2 INCH GATE VALVE	18	EA
623-06902	FUTURE CONNECTION STUB	42	EA
623-07008	1 INCH WATER METER	7	EA
623-07500	SOIL MOISTURE SENSORS WITH DECODER	17	EA
623-07607	1-1/2 INCH HYDROMETER WITH DECODER	7	EA

**CITY AND COUNTY OF DENVER  
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

**STATEMENT OF QUANTITIES**

<b>ITEM NO.</b>	<b>DESCRIPTION</b>	<b>ESTIMATED</b>	<b>UNIT TYPE</b>
623-08153	TWO WIRE CONTROLLER	7	EA
625-00000	CONSTRUCTION SURVEYING	1	LS
626-00000	MOBILIZATION	1	LS
630-00007	TRAFFIC CONTROL INSPECTION	110	DAY
630-00012	TRAFFIC CONTROL MANAGEMENT	275	DAY
630-80340	PEDESTRIAN BARRICADE (ADA)	8	EA
630-80341	CONTRUCTION TRAFFIC SIGN (PANEL SIZE A)	28	EA
630-80342	CONTRUCTION TRAFFIC SIGN (PANEL SIZE B)	4	EA
630-80355	PORTABLE MESSAGE SIGN PANEL	4	EA
630-80356	ADVANCE WARNING FLASHING OR SEQUENCING ARROW PANEL (A TYPE)	2	EA
630-80360	DRUM CHANELIZING DEVICE	56	EA
630-80363	DRUM CHANELIZING DEVICE (WITH LIGHT)(FLASHING)	56	EA
630-80380	TRAFFIC CONE	280	EA
Force Accounts			
700-70592	F/A SURVEY MONUMENTATION	1	FA
700-70010	F/A MINOR CONTRACT REVISIONS	1	FA
700-70037	F/A CONTAMINATED SOIL	1	FA
700-70597	F/A ON THE JOB TRAINEE	1	FA
700-70599	F/A GROUNDWATER CONTAINERIZATION	1	FA