

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

STATEMENT OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT
202-00019	REMOVAL OF INLET	5	EA
202-00033	REMOVAL OF SIPHON	5	EA
202-00200	REMOVAL OF SIDEWALK	630	SY
202-00201	REMOVAL OF CURBHEAD	150	LF
202-00203	REMOVAL OF CURB AND GUTTER	6,150	LF
202-00204	REMOVAL OF COMBO CURB/GUTTER	3,700	LF
202-00205	REMOVAL OF DETACHED SIDEWALK	1,925	SY
202-00208	REMOVAL AND RESET FLAGSTONE (INCLUDES SALVAGE AND STORAGE)	50	SY
202-00210	REMOVAL OF CONCRETE PAVEMENT	3,580	SY
202-00212	REMOVAL OF CONCRETE ADA CURB RAMP	6,300	SY
202-00213	COMPRESSED AIR EXCAVATION FOR TREE ROOTS	50	HR
202-00214	WATER EXCAVATION FOR TREE ROOTS	50	HR
202-00215	TREE PROTECTION FENCE	10	EA
202-01000	REMOVAL AND RESET OF FENCE	40	LF
203-00200	UNCLASSIFIED EXCAVATION	125	CY
203-02330	3-MAN LABOR CREW	100	HR
206-00065	STRUCTURE BACK FILL (FLOW FILL)	15	CY
208-00050	STORM DRAINAGE INLET PROTECTION	150	EA
210-00810	RESET GROUND SIGN	50	EA
210-04010	ADJUST MANHOLE/PULLBOX	30	EA
210-04011	ADJUST INLET FRAME AND ADJUSTABLE CURBHEAD	15	EA
210-04020	RESET INLET GRATE,FRAME, AND ADJUSTABLE CURB BOX (NEW CASTING)	30	EA
212-00050	SODDING	130	SF
212-01200	RESTORE LANDSCAPING	14,000	SF
212-01201	AMENDED TOP SOIL OR LANDSCAPE PLANTER'S SOIL MIX	200	CY
304-06000	AGGREGATE BASE COURSE	1,350	TON
403-00720	HBP PATCH/OVERLAY	2,750	TON
412-00000	24-HOUR HIGH EARLY STRENGTH CONCRETE	270	CY
412-00001	ADD PIGMENT TO CONCRETE	25	CY
412-00100	GEO TECH MATERIAL TESTING CONCRETE	25	EA
412-00400	4" CONCRETE PAVEMENT	20	SY
412-00600	6" CONCRETE PAVEMENT	1,725	SY
412-00800	8" CONCRETE PAVEMENT	1,725	SY
412-01000	10" CONCRETE PAVEMENT	75	SY
412-01200	12" CONCRETE PAVEMENT	35	SY
413-00100	CONCRETE PATCHING (STRUCTURAL SURFACE REPAIR <2" DEPTH)	60	SF-IN

**CITY AND COUNTY OF DENVER
DEPARTMENT OF TRANSPORTATION AND INFRASTRUCTURE**

STATEMENT OF QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT
601-00100	PAVESTONE STACKED PRE-CAST WALL BLOCK	150	SF
601-00400	REINFORCED VARIABLE HEIGHT CONCRETE RETAINING WALL	70	SF
601-06150	CONCRETE PATCHING (STRUCTURAL CURB REPAIR)	135	LF
604-14050	NUMBER 14 INLET (L=6')	3	EA
604-16050	SINGLE NUMBER 16 INLET	3	EA
604-18050	CHASE DRAIN AND TREAD PLATE (1' WIDTH)	5	LF
604-20050	CHASE DRAIN AND TREAD PLATE (2' WIDTH)	5	LF
608-00000	CONCRETE SIDEWALK	630	SY
608-00005	DETACHED CONCRETE SIDEWALK	1,925	SY
608-00010	CONCRETE CURB RAMP	6,300	SY
608-00018	TRUNCATED DOMES (SPECIAL CAST IRON) MATERIAL ONLY	350	SF
609-20000	CONCRETE GUTTER OVERLAY	1,000	LF
609-21020	CURB & GUTTER TYPE II, SECTION 2B	6,000	LF
609-21023	CURB & GUTTER TYPE IIB (9") CURBHEAD	150	LF
609-22021	COMBO CURB, GUTTER & SIDEWALK (2'-8")	2,700	LF
609-22025	COMBO CURB, GUTTER & SIDEWALK (3'-11")	630	LF
610-00026	MEDIAN COVER MATERIAL (6" PATTERNED COLORED CONCRETE)	30	SY
613-07000	RESET PULL BOX	30	EA
623-00204	SPRINKLER SYSTEM/ADJUST SPRINKLER HEAD	700	EA
623-00205	SPRINKLER SYSTEM/NEW SPRINKLER HEAD	700	EA
623-00505	SPRINKLER SYSTEM/IRRIGATION RECONSTRUCTION	6,500	LF
630-00000	TRAFFIC CONTROL - ARTERIAL/COLLECTOR	50	DAY
630-00002	TRAFFIC CONTROL - LOCAL	80	DAY
630-00003	TRAFFIC CONTROL - UNIFORMED TRAFFIC CONTROL	16	HR